BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of the work :- Construction of DWCC Centre at Bagalagunte in Ward No

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork in surface excavation in Ordinary Soil for Levelling and Lowering the ground manually (other than foundation of buildings culverts road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	Cum	24.00	169.56	Rupees One hundred & Sixty Nine & Fifty Six Paise Only
2	Earth work excavation for foundation of building culverts, water supply sanitary lines and electrical conduits either pits or in trenches 1.5m and above in width in Hard soil	Cum	92.98	305.64	Rupees Three hundred Five & Sixty Four Paise Only
3	Providing and Laying in position plain cement concrete of Mix 1:3:6 with OPC Cement @ 160kgs with 40mm down size graded granite metal coarse aggregate 0.85cum and fine aggregate @ 0.57Cum machine mixed concrete laid in layers not exceeding 15cm thick well compacted in foundation plinth including cost of materilas, HOM of machineries curing complete as per specification	Cum	7.75	5449.68	Rupees Five thousand Four hundred forty Nine & Sixty Eight Paise Only
4	Providing and filling in foundation with granite/trap broken metal of 100 MM and down size with approved sand including hand packing ramming watering including cost of all materials and labour charges and with all lead and lift etc complete as per specification and the direction of the Engineer in charge	cum	17.17	2283.12	Rupees Two thousand two hundred eighty three & Twelve Paise Only
5	Providing and laying cement concrete using 20mm down size granite jelly of ready mixed concrte (RMC) for R C C works laid in 15cms thick and well compacted vibrating curing finishing with necessary cement mortar with all lead lifts etc complete (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete M-25 (1:1:2:3) for raft foundation column footing, main and secondary beams)	Cum	9.54	6550.20	Rueeps Six thousand Five hundred fifty & Twenty paise only
6	Providing and removing a centering, shuttering, strutting, propping etc and removal of form work for a foundation, footing bases of column for mass concrete including cost of all materials, labours, complete as per specifications	Sqm	31.81	249.48	Rupees Two hundred forty nine & forty eight Paise only

Executive Engineer

EXECUTIVE ENGINEER-4
SPECIAL DIVISION
BENGALURU-560 010

Scanned by CamScanner

7	oviding and Laying in position reinforced cement crete of design mix M20 with OPC cement @ 320Kgs wit 20mm and down size graded granite metal course aggregate @ 0.878cum and fine aggregate @ 0.459cum, with superplastisiser @ 3ltr confirming to IS 9103-1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground level for roof slab, stairecase, lintels, retaining wall , return wall, wall (any thickness) including attahed plasters, column , piers, abutmentspillers, posts, struts, buttresses, string or laceing courses, parapets, coping, bed blocks, anchor hooks plain window cill, fillets, etc.., including cost of all materials, Labours, HOM of Machineries, curing complete as per specification	Cum	**4.46**	**6876.36**	Rupees Six thousand Eight hundred seventy Six & Thirty Six Paise Only
8	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square /rectangular / polygon in plan including cost of all materials, labour complete as per specification.	Sqm	**20.34**	**395.28**	Rupees Three hundred ninty Five & Twenty Eight Paise Only
9	Providing and Laying in position reinforced cement concrete of design mix M25 with OPC cement @ 320Kgs with 20mm and down size graded granite metal course aggregate @ 0.878cum and fine aggregate @ 0.459cum, with superplastisiser @ 3ltr confirming to IS 9103-1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground level for roof slab, stairecase, lintels, retaining wall , return wall, wall (any thickness) including attahed plasters, column , piers, abutmentspillers, posts, struts, buttresses, string or laceing courses, parapets, coping, bed blocks, anchor hooks plain window cill, fillets, etc.., including cost of all materials, Labours, HOM of Machineries, curing complete as per specification	Cum	**6.13**	**6876.36**	Rupees Six Thousand Eight hundred Seventy six & Thirty Six Paise only
10	Providing and removing centring, shuttering,propping etc., and removal of form work for vertical surface such as walls at any thickess, including attached pilastrers, buttresses, plinth and srring courses cost of all materials,labour complete as per specifications,	Sqm	**58.71**	**316.44**	Ruppes Three hundred Sixteen & Forty four Paise Only
11	Providing and constructing grinite /trap/basalt size stone masonry in foundation with cement motar 1:6 stone hammer dressed in coursenot less than 20cm high bond stones at two m apart in each course including cost of materils ,lobour curing complete as per specification	Sqm	**22.88**	**4521.96**	Rupees Four Thousand five hundred twenty one & ninty Six Paise Only
12	Providing ruled pointing to coursed stone masonry with cement mortar 1:3 , 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials,labour,curing complete as per specification	Sqm	**22.88**	**37.80**	Rupees Thirty Seven & Eighty Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

	Filling available excavated earth (excluded rock) in sides of foundation upto plinth in layers not exceeding 30 cms in depth compacting each deposited layers by ramming after watering with load upto 60mm and lift up to 1.5m including cost of all labours complete as per specification	Cum	92.58	137.16	Rupees One hundred Thirty Seven & Sixteen paise Only
14	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 (brick per sqmm table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	SQM	166.58	7219.80	Rupees Seven thousand Two hundred & Nineteen & Eighty Paise Only
15	Providing and laying in position reinforced cement of mix M25 with OPC cement @424kgs, with 12mm and down size graded granite metal coarse aggregates @ 0.517cum and fine aggregates @ 0.345cum, with superplastisiser @0.225lts, machine mixed well compacted for plain chajja of 7.5 cms averages thickess, upto ground upto ground floor level including cost of all materials ,labours, HOM of machinery , finishing,curing,complete as per specification	Sqm	7.66	492.48	Rupees Four hundred Ninty Two & Forty Eight Paise Only
16	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specification	Sqm	7.66	291.60	Rupees Two hundred Ninty One & Sixty Paise Only
17	Providing and Laying in position reinforced cement concrete of design mix M25 with OPC cement @ 320Kgs with 20mm and down size graded granite metal course aggregate @ 0.878cum and fine aggregate @ 0.455cum, with superplastisiser @ 3ltr confirming to IS 9103:1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground level for roof slab, staircase, lintels, retaining wall , return wall, wall (any thickness) including attached plasters, column , piers, abutmentspullers, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor hooks plain window cill, fillets, etc , including cost of all materials, Labours, HOM of Machineries, curing complete as per specification	Cum	0.72	6876.36	Rupees Six thousand Eight hundred seventy Six & Thirty Six Paise Only
18	Providing and removing centering, shuttering, strutting, propping etc , an removal of form work for sides and soffits of beams, beam haunchings, cantilever, girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications	Sqm	9.00	276.48	Rupees Two hundred seventy six & forty eight Paise Only
19	Providing and laying to required line and slope roofing with semi corrugated (Trafford) asbestos cement sheet 6mm thick fixed with galvanised iron J or L hooks, blots and nits 8mm dia C.I plain and bitumen washers, over the existing purlins, rafters and trusses including cost of materials, labour, complete as per specifications	sqm	72.00	426.60	Rupees Four hundred twenty six & sixty Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

20	Fabricating, supplying & erecting M.S. angular Truss for all spans as approved de. The entiretruss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification	kgs	960.28	126.36	Rupees One hundred twenty six & Thirty Six Only
21	Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully open able as per approved drawings using Z angles of 25x33x3mm, weighing 1.419Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm thick reeded glass with teakwood beading of required size, all steel section should confirm to I.S. 7452:1990, 4nos, of holdfasts of approved size section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be thoroughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per	Sqm	11.40	3812.40	Ruppes Three thousand Eight hundred twelve & Forty Paise Only
22	SOLID PANEL PRELAM PVC DOOR SHUTTER : Providing and fixing 30 mm thick factory made rgid foam with both side Pr- laminated Panelled Door Shutters made from M.S. tube of 19x19 mm, 19 gauge for styles and 15x15mm for top and bottom rails, covered with heat moulded Pre-laminated PVC C Channel of 5mm thick sheet and 30x50mm wide to form styles and 5mm thick and 75mm wide Pre-laminated PVC Sheets for top rail, lock rail and bottom rail on either side and 5mm thick, 20 mm wide cross PVC sheet as gap insert for top rail and bottom rail, Panelling of 5mm thick PVC sheet Pre-laminated on either side fitted in the M.S. frame, Sealed to the styles and rails with PVC Designer beading on either side and joined together with solvent cement adhesive etc., Complete as per manufacturers specification and direction of Engineer-in-charge fixed to frames with 3 nos. of 75	sqm	3.15	4368.60	Rupees Four thousand Three hundred & Sixty Eight & Sixty Paise Only

Executive Engineer

Signature of the Contractor

EXECUTIVE ENGINEER-1
KRIDL, BBMP DIVISION
BENGALURU-560 010

Scanned by CamScanner

23	Providing and fixing pull and push type rolling shutters of approved maki out of 18guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements for inside & outside locking with push & pull operations complete including puilling hooks, 4nos, handles with all fittings and accessories, painted with a coat of red lead paint (Without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3m x 2.8m Specification	sqm	6.50	3033.72	Rupees Three thousand Thirty Three & Seventy Two Paise Only
24	Providing and fixing top covers made out of 20guage M.S sheet over pull and push rolling shutters bent to shape including cost of red lead primer cost of painting, materils, labour HOM of machinery complete as per specifications,	sqm	6.50	3033.72	Rupees Three thousand Thirty Three & Seventy Two Paise Only
25	Providing and fixing M.S. grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	sqm	306.18	90.10	Rupees Ninty & Ten Paise Only
26	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding of corners wherever required smooth rendering, providing and removing scaffolding, including cost of all materials, labours, curing, complete as per specificatioon	sqm	138.61	238.68	Rupees Two hundred Thirty Eight & Sixty Eight Paise Only
27	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications\	Sqm	138.61	27.00	Rupees Twenty seven Only
28	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding of corners wherever required smooth rendering, providing and removing scaffolding, including cost of all materials, labours, curing, complete as per specificatioon	sqm	127.64	238.68	Rupees Two hundred Thirty Eight & Sixty Eight Paise Only
29	Flooring with 20mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab including cost of materials, labour, curing, polishing complete as per specification.	Sqm	39.02	1294.92	Rupees One thousand Two hundred Ninty four 7 Ninty Two Paise Only
30	Providing skirting, dado, rises of steps with Color glazed tiles 30 x 60 cms, 6mm thick on 6mm thick ementplaster 1:3 and jointed with white cement slurry over rough plaster surface excluding cost of rough plastered surface which should be measured and paid seperately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications	Sqm	15.33	1573.04	Rupees One thousand Five hundred Seventy three & Four Paise Only

Signature of the Contractor

Executive Engineer

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Scanned by CamScanner

	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including primary coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing surface even and sand paper smooth, cost of materials, labour, complete ass per specifications	Sqm	138.61	76.68	Rupees Seventy Six & sixty Eight paise only
32	Providing and applying two coats of wall putty to inside plaster walls and ceiling using white cement putty. Scapping and leveling the syurface using steel blade and preparing the surface even and smooth by using different grade, sand papers including cost of all materilas, cost of labour, scaffolding etc.., complete as per specification	Sqm	138.61	60.48	Rupess Sixty & forty eight Paise only
33	Providing and finishing External walls in two coats over one coat of 100% acrylic silicon glaze primer with antifungal paint for coat of approved brand and shade to give an even shade after thouroughly brooming the surface to remove all dirt and loose powdered materials, free from mortar drops and other foreign matter cost of materilas , labour, complete as per specification	sqm	127.64	163.08	Rupees One hundred Sixty three & Eight Paise Only
34	Providing white washing to new wall surface in two coats with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications	sqm	127.64	8.64	Rupees Eight & Sixty Four Paise Only
35	Providing and applying enamel metal paint two coats(excluding primming coat) overnew steel or other metal surface breshing to give an even shade after cleaning oil, grease, dirt, and other forighn matter, including cost of all materials, labours, complete as per specification	Sqm	129.90	88.56	Rupees Eighty Eight & Fifty Six Paise Only
36	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and achoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Qtl	2.12	76329.00	Rupees Seventy Six Three hundred twenty Nine Only
37	Supplying and wiring adoptiong loop system in existing PVC conduit /casing caping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose legnth in a wood/PVC round block, complete for each outlet	No	6.00	175.00	Rupees One hundred Seventy five Only
			4.00	368.00	Rupees Three hundred sixty eight only
38	Supplying 6A flush /projected type socket and a 6 amps flush/projected type SP switch either surface mounting in a gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required	No	12.00	91.00	Rupees Ninty one only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete	Each	6.00	98.00	Rupees Ninty eight only
40	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulated etc.., and fixing on existing wooden or metal box using N.F. screws	Sq. cmt	7.00 3226.00	68.00 0.22	Rupees sixty eight only Rupees twenty two paise only
41	Extra for groove cutting, plastering and colour washing for embedding PVC conduit/GI pipe and plastering finishing the wall upto wall surface complete upto 50mm conduit in brick in wall	Rmtr	220.00	14.00	Rupees Fourteen only
42	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charcoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per IS1 specification 7.3.3 of IS 732 using 12 mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122 mm dia	Each	1.00	3000.00	Rupees Three thousand Only
43	Supplying and fixing of porcelain fuse chanel with cut out on existing wooden/panel using ncessary nuts, bolts and washers etc complete	Each	6.00	54.00	Rupees Fifty Four Only
44	Supplying 20mm dia 2mm thick heavy guage PVC conduit pipe with suitable size bends, metal junction boxes, adhesive paste etc and running before concreting the slabs. The conduit should be tied to the reinforcement roads by using binding wire and unused ways of junction boxes and pipe ends should be covered using PVC and enclosures and run with 18 SWG GI fish wire run throughout the conduit wherever necessary.	Rmtr	130.00	32.00	Rupees Thirty Two Only
45	Supplying and fixing PBBC brass/Bakelite straight or slant batten holder and wiring, within 60W/230 Volts lamps	No.	6.00	60.00	Rupees Sixty only
46	Supply patty type fluorescent tube light fitting of 4 feet 40 watts fluorescent tube of 230 volts made of M.S. sheet and stove enameled with heavy duty polyfill aluminum choke, starter, locking type brass contact holders mounted on foldable type sheet base fully wired.for use on 230 volts AC supply including 1 Nos 4'-36/40 watts fluorecent tube A Group	No	12.00	400.00	Rupees Four hundred only
47	Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 1.50 Sqmm materials	Rmtr	400.00	15.00	Rupees Fifteen Only
48	Supplying and running of GI / Copper conductor for grounding & (along with other wires of CTS or conduit system of wiring) using if necessary suitable size clamps bolts nuts and washers etc.	Rmtr	24.00	221.00	Rupees Two hundred Twenty One only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

	Supplying and fixing miniature circuit breakers/Isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as required	No.	6.00	370.00	Rupees Three hundred Seventy only
50	Supplying capacitor type ceiling fan complete with down rod blades, shakle, regulator canopies etc., for operation on 230 volts, 50 cycles, Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved (Almanord, Unique ISI, Anchor, Crompton, Khaitan, Bajaj, Usha, Johnson make)	Nos	6.00	1900.00	Rupees One thousand Nine hundred Only
51	Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely.	Nos	6.00	105.00	Rupees One hundred Five Only
52	Supplying and fixing 32mm dia class A GI pipe bracket upto 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluoroscent tube street light fitting of all capacities to GI or CI or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete	Nos	6.00	685.00	Rupees Six hundred Eighty Five Only
53	Digging of trench of 0.6m deep x 0.50mtr wide refiling the trench to the required ground level and consolidating etc., complete In Hard Soil	Rmtr	20.00	50.00	Rupees Fifty Only
54	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold watersupply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing This includes jointing ofpipes and fittings with one step CPVC solvent cement & the cost ofcutting chases & making good the same including testing of jointscomplete (Concealed work including cutting chases and good the wallsetc) 20mm nominal OD pipes	M	50.00	226.80	Rupees Two hundred twenty six & Eighty Paise only
55	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold watersupply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing This includes jointing ofpipes and fittings with one step CPVC solvent cement & the cost ofcutting chases & making good the same including testing of jointscomplete. (Concealed work including cutting chases and good the wallsetc.) 25mm nominal OD pipes	M	50.00	270.00	Rupees Two hundred Seventy Only
56	Providing and fixing Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot) size 12.5cms x7.5cms	Each	3.00	307.80	Rupees Three hundred seven & Eighty Paise Only
57	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia	Each	3.00	172.80	Rupees One hundred Seventy two & Eighty Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal boreincluding cost of all materials, labour and HOM of equipments with allleads complete as per specifications.	Each	**2.00**	648.00	Rupees Six hundred Forty Eight Paise
59	Providing and fixing to wall, ceiling and floor, low densitypolyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outsidediameter with special flange, compression type fittings, wall clips, makinggood the wall, ceiling and floor, including cost of all materials, labourcharges, HOM of equipments and testing complete as per specifications	Mtr	**36.00**	574.56	Rupees Five hundred Seventy Four & Fifty Six Only
60	Constructing brick masonry inspection chamber 455x610 mm, and 450 mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5 in C.I.cover with frame (light duty 455x610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) R CC Top slab with cement concrete1:2:4 mix 20 mm and downsize granite metal, foundation concrete 1:5:10 with 40 mm and down size granite metal inside plastering 12 mm rhick with cement mortar 1:3 finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications	Each	**1.00**	7604.28	Rupees Seven thousand Six hundred Four & Twenty Eight Paise Only
61	Providing and fixing white vitreous china clay, surgeon type wash basin size 660 x 460 with a pair of 15 mm C.P. brass pillar taps with pair of elbow operated levers, C.I./M.S. brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour, curing complete as per specification	Unit	**2.00**	4945.32	Rupees Four thousand Nine hundred forty five & Thirty Two Paise Only
62	Providing and fixing in position brass bib cock of approved quality 25 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads, complete as per specifications	Each	**2.00**	293.76	Rupees Two hundred Ninty three & Seventy six Paise Only
63	Providing and fixing white vitreous china clay, water closet Orissa Pattern of size 580 x 440 mm with integral type footrest, 100mm S or P trap, 10 litre low level, P.V.C. flushing cistern (all are approved make) with fittings, C.I./M.S. brackets, 32 mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25 mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour, curing complete as per	Pan	**2.00**	4682.88	Rupees Four thousand six hundred eighty two 7 Eighty Eight Paise Only

EXECUTIVE ENGINEER-4
BBMP/BBMP DIVISION
BENGALURU-560 010

Signature of Contractor

Executive Engineer

Scanned by CamScanner

4	Providing and placing on terrace, polyethylene waterstorage tanks with manhole lid and suitable locking arrangements,making holes of suitable diameter for inlet, outlet and over flow pipes,including cost of all materials, labour, transport charges, HOM ofequipments and testing complete as per specifications.(For 1000 litre	Nos	1.00	9144.36	Rupees Nine thousand One hundred Forty four & Thirty Six Only
65	Providing and fixing 453x357mm rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing incluidng cost of materials, labour complete as per specifications	Unit	2.00	1274.40	Rupees One thousand Two hundred Seventy four & Forty Paise only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Scanned by CamScanner